
STANTEC CONSULTING MICHIGAN - ENGINEER'S OPINION OF CONSTRUCTION COST

Stantec Pittsfield Township Washtenaw County, Michigan Pittsfield Glen at Textile Road Crossing					
Conceptual X Preliminary inal (As Bid)			Project Number: Prepared By: Checked By: Date:		2075001316 CRW CAM October 11, 2022
	DESCRIPTION	QUANT.	UNIT	UNIT COST	TOTAL COST
ittsfield Gle	en at Textile Road Midblock Crossing		·		
1	General Conditions/Mobilization/Permits (10% Max)	1	LS	\$7,300	\$7,300
2	Contractor Construction Layout & Staking	1	LS	\$3,000	\$3,000
3	Traffic Control & Maintenance	1	LS	\$7,500	\$7,500
4	Pedestrian Barricades	4	EA	\$300	\$1,200
5	Audio-Video Project	1	LS	\$2,000	\$2,000
6	Proposed Silt Fence/SESC	100	LF	\$2.50	\$250
7	Soil Undercut (Special) - Allowance	10	CY	\$70	\$700
8	Project Clean-Up	1	LS	\$5,000	\$5,000
9	Curb Removal	50	LF	\$15	\$750
10	Earthwork and Fine Grading (includes ditching & topsoil)	100	LF	\$50	\$5,000
11	Concrete Sidewalk (Includes 4" Sand Subbase)	250	SF	\$10	\$2,500
12	Concrete Sidewalk Approaches/Ramps (Includes 4" Sand Subbase)	500	SF	\$15	\$7,500
13	Curb Ramp Opening	75	LF	\$35	\$2,625
14	Landscaping Restoration (5ft wide each side)	125	SY	\$8	\$1,000
15	Double-Sided RRFB, Solar Power (includes pedestal and pushbutton)	2	EA	\$12,000	\$24,000
16	HMA Hand Patching - Allowance	5	TON	\$300	\$1,500
17	Pavement Markings (includes removal and crosswalk)	200	FT	\$15	\$3,000
18	Signage (icludes special RRFB signage and steel posts)	50	SF	\$100	\$5,000
		CONST	RUCTION	N SUBTOTAL	\$79,900
CONSTRUCTION CONTINGENCIES 20%					\$16,000
TOTAL OPINION OF CONSTRUCTION COST					\$95,900

CONTRACTOR's method of determining prices, or over competitive bidding or market conditions. Opinions of probable project costs and construction costs provided herein are made on the basis of the ENGINEER's professional judgment and experience. The ENGINEER cannot and does not guarantee that proposals, bids or actual project or construction costs will not vary from the prepared opinion of probable cost.

Pittsfield Glen



2022.10.19

